

ELECTRICAL ESTIMATE

Customer:	All Weather Specialists
Project:	100 Amp Heat Strip Circuit Installation
Property Address:	7414 South Drexel, Chicago, Illinois
Location:	Basement to Air Handler
Date:	April 19, 2026

Scope of Work:

Provide labor and material to install one new dedicated 100-amp, 240-volt electrical circuit for HVAC heat strip equipment. Approximate circuit distance is 60 feet from the electrical panel to the air handler/heat strip location.

Work includes: Install one new 100A two-pole breaker Install properly sized conductors and grounding conductor
Install EMT/conduit and fittings as required Terminate wiring at heat strip equipment Circuit testing and verification
Panel labeling and final operational check Excludes drywall repair, painting, permit fees, and HVAC equipment repairs or replacement.

Description	Amount
100A Heat Strip Circuit Installation – 60 Ft Run	\$1,400.00

Total Estimated Cost: \$1,400.00

Thank you for the opportunity to provide electrical services.

Distinctive Electrical Services Corp.