



# BLACKTECH SOLUTIONS CORP

14076 Lincoln Ave, Dolton, IL 60419

ESTIMATE NO. BSC-E-2026-BIS002-A

## ESTIMATE

OPTION A — PREMIUM

### CONTRACTOR

#### Blacktech Solutions Corp

14076 Lincoln Ave

Dolton, IL 60419

(773) 449-9396

estimates@blacktechsolutionscorp.com

### PROJECT

#### 6833 S Bishop Street

Chicago, IL 60636

Single-Family Residential

Full Renovation — 1,813 GSF

Permit #101082093

### JOB DETAILS

JOB NAME

**6833 S Bishop — Full Rewire**

ESTIMATE #

**BSC-E-2026-BIS002-A**

DATE

**06/15/2026**

OPTION

**Premium**

| #                                | PRODUCT / SERVICE                                                                                                                      | QTY | UNIT | RATE       | AMOUNT      |
|----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|-----|------|------------|-------------|
| ADMINISTRATION                   |                                                                                                                                        |     |      |            |             |
| 1                                | <b>Electrical Permit — City of Chicago</b><br>Permit #101082093 — Self-Cert 2019 CBC, full building permit electrical scope            | 1   | Flat | \$1,000.00 | \$1,000.00  |
| LABOR — STANDARD RATE (\$150/HR) |                                                                                                                                        |     |      |            |             |
| 2                                | <b>Demolition &amp; Prep</b><br>Remove existing electrical meter, cut & cap abandoned circuits, prep for new work                      | 16  | Hrs  | \$150.00   | \$2,400.00  |
| 3                                | <b>Service Entrance &amp; Riser</b><br>New 2" RMC HW riser, 3#3/0 copper, weatherhead to ComEd pole, new exterior meter                | 24  | Hrs  | \$150.00   | \$3,600.00  |
| 4                                | <b>Main Distribution Panel</b><br>New 200A panel (Type 1 enclosure), main disconnect, neutral link, all terminations                   | 16  | Hrs  | \$150.00   | \$2,400.00  |
| 5                                | <b>Grounding System</b><br>Ground rod (5/8"×10'), UFER connection, exothermic welds, bonding, TGB, photo documentation                 | 16  | Hrs  | \$150.00   | \$2,400.00  |
| 6                                | <b>Rough-In — Branch Circuits</b><br>All new conduit, wire pulls, box placement throughout 1,813 GSF (2 levels + exterior)             | 80  | Hrs  | \$150.00   | \$12,000.00 |
| 7                                | <b>Trim Out — Devices &amp; Fixtures</b><br>Install all receptacles, switches, light fixtures, smoke/CO detectors per electrical plans | 40  | Hrs  | \$150.00   | \$6,000.00  |
| MATERIALS — PREMIUM GRADE        |                                                                                                                                        |     |      |            |             |
| 8                                | <b>200A Panel + Breakers</b><br>Square D QO or equivalent, 42-space, copper bus, AFCI/GFCI breakers per code                           | 1   | Lot  | \$2,800.00 | \$2,800.00  |
| 9                                | <b>Wire &amp; Conduit</b><br>Copper THHN/THWN, 3#3/0 service, #12/#14 branch, 2" RMC riser, EMT throughout                             | 1   | Lot  | \$3,200.00 | \$3,200.00  |
| 10                               | <b>Devices &amp; Fixtures</b><br>Decora receptacles/switches, LED recessed lights, exterior fixtures, smoke/CO detectors               | 1   | Lot  | \$2,500.00 | \$2,500.00  |

|                            |                    |
|----------------------------|--------------------|
| Labor (192 hrs @ \$150/hr) | \$28,800.00        |
| Materials                  | \$8,500.00         |
| Permit Fee                 | \$1,000.00         |
| <b>TOTAL — OPTION A</b>    | <b>\$38,300.00</b> |

 **SAVINGS VS. OPTION B**

Option B (Value) saves **\$17,600** using at-cost labor (\$75/hr) and standard-grade materials.  
See estimate **BSC-E-2026-BIS002-B** for the value option.

**SCOPE NOTES**

- Full electrical rewire per Self-Cert Permit #101082093 and electrical drawings by Karl F. Guider (Guidergroup LLC).
- Includes: new service entrance, meter, 200A panel, grounding system, all branch circuits, devices, and fixtures.
- Excludes: low-voltage/data cabling, AV systems, generator/backup power, solar integration (available as add-on).
- All work per 2019 Chicago Electrical Code (Title 14E) with local amendments.
- Grounding system includes photo documentation for owner records per spec.
- Contractor to coordinate meter installation with ComEd.

PREPARED BY

**Derrell Black — Blacktech Solutions Corp**

ACCEPTED BY

Thank you for the opportunity! · Blacktech Solutions Corp · (312) 965-2782 · [estimates@blacktechsolutionscorp.com](mailto:estimates@blacktechsolutionscorp.com)