



BLACKTECH SOLUTIONS CORP

14076 Lincoln Ave, Dolton, IL 60419

ESTIMATE NO. BSC-E-2026-BIS002-B

ESTIMATE

OPTION B — VALUE

CONTRACTOR

Blacktech Solutions Corp

14076 Lincoln Ave

Dolton, IL 60419

(773) 449-9396

estimates@blacktechsolutionscorp.com

PROJECT

6833 S Bishop Street

Chicago, IL 60636

Single-Family Residential

Full Renovation — 1,813 GSF

Permit #101082093

JOB DETAILS

JOB NAME

6833 S Bishop — Full Rewire

ESTIMATE #

BSC-E-2026-BIS002-B

DATE

06/15/2026

OPTION

Value

#	PRODUCT / SERVICE	QTY	UNIT	RATE	AMOUNT
ADMINISTRATION					
1	Electrical Permit — City of Chicago Permit #101082093 — Self-Cert 2019 CBC, full building permit electrical scope	1	Flat	\$1,000.00	\$1,000.00
LABOR — AT-COST RATE (\$75/HR)					
2	Demolition & Prep Remove existing electrical meter, cut & cap abandoned circuits, prep for new work	16	Hrs	\$75.00	\$1,200.00
3	Service Entrance & Riser New 2" RMC HW riser, 3#3/0 copper, weatherhead to ComEd pole, new exterior meter	24	Hrs	\$75.00	\$1,800.00
4	Main Distribution Panel New 200A panel (Type 1 enclosure), main disconnect, neutral link, all terminations	16	Hrs	\$75.00	\$1,200.00
5	Grounding System Ground rod (5/8"×10'), UFER connection, exothermic welds, bonding, TGB, photo documentation	16	Hrs	\$75.00	\$1,200.00
6	Rough-In — Branch Circuits All new conduit, wire pulls, box placement throughout 1,813 GSF (2 levels + exterior)	80	Hrs	\$75.00	\$6,000.00
7	Trim Out — Devices & Fixtures Install all receptacles, switches, light fixtures, smoke/CO detectors per electrical plans	40	Hrs	\$75.00	\$3,000.00
MATERIALS — STANDARD GRADE					
8	200A Panel + Breakers Siemens or Eaton, 42-space, aluminum bus, standard breakers per code	1	Lot	\$1,800.00	\$1,800.00
9	Wire & Conduit Copper THHN/THWN, 3#3/0 service, #12/#14 branch, 2" RMC riser, EMT throughout	1	Lot	\$2,200.00	\$2,200.00
10	Devices & Fixtures Standard receptacles/switches, builder-grade LED lights, exterior fixtures, smoke/CO detectors	1	Lot	\$1,300.00	\$1,300.00

Labor (192 hrs @ \$75/hr)	\$14,400.00
Materials	\$5,300.00
Permit Fee	\$1,000.00
TOTAL — OPTION B	\$20,700.00

💰 YOU SAVE \$17,600 VS. OPTION A

Option A (Premium): **\$38,300** — standard rate (\$150/hr) + premium materials (Square D QO, Decora devices).
Option B (Value): **\$20,700** — at-cost labor (\$75/hr) + standard-grade materials.
Same scope, same code compliance — different finish level and labor rate.

SCOPE NOTES

- Full electrical rewire per Self-Cert Permit #101082093 and electrical drawings by Karl F. Guider (Guidergroup LLC).
- Includes: new service entrance, meter, 200A panel, grounding system, all branch circuits, devices, and fixtures.
- Excludes: low-voltage/data cabling, AV systems, generator/backup power, solar integration (available as add-on).
- All work per 2019 Chicago Electrical Code (Title 14E) with local amendments.
- Grounding system includes photo documentation for owner records per spec.
- Contractor to coordinate meter installation with ComEd.

PREPARED BY

Derrell Black — Blacktech Solutions Corp

ACCEPTED BY

Thank you for the opportunity! · Blacktech Solutions Corp · (312) 965-2782 · estimates@blacktechsolutionscorp.com