



BLACKTECH SOLUTIONS CORP

Material Quote Request — 4823 S Prairie Ave, Chicago, IL 60615

Project: Two-Flat Electrical Rehab — Full Project (Phase 1 + Phase 2) | BSC-E-2026-PR002 & PR003

DISTRIBUTION EQUIPMENT — Phase 1 (PR002)

Qty	Description	Unit
1	3-Gang Meter Bank — 200A per gang, ComEd approved (Eaton/Milbank), NEMA 3R enclosure	each
1	200A Main Service Panel — Eaton BR 42-space, NEMA 1, copper bus	each
2	100A Sub-Panel — Eaton BR 20-space, main breaker (one per unit)	each
1	Feeders & Conduit — 2/0 AWG aluminum SER, EMT conduit, connectors, fittings, grounding	lot

WIRE — THHN (EMT Conduit, Chicago Code)

Qty	Description	Unit
6	12 AWG THHN Stranded — 500ft spools (Black/Red/White/Green — 20A branch circuits & home runs)	spool
4	14 AWG THHN Stranded — 500ft spools (Black/White/Green — 15A lighting & general receptacle circuits)	spool
2	10 AWG THHN Stranded — 500ft spools (for dedicated appliance circuits)	spool

DEVICES

Qty	Description	Unit
40	20A Tamper-Resistant Duplex Receptacle — White, spec grade	each
8	20A GFCI Receptacle — White, tamper-resistant, self-test	each
16	15A Single Pole Switch — White, spec grade	each
8	15A 3-Way Switch — White, spec grade	each
4	LED-Compatible Dimmer Switch — Single pole, white	each
40	Single Gang Face Plate — White, unbreakable nylon	each
8	2-Gang Face Plate — White, unbreakable nylon	each
4	3-Gang Face Plate — White, unbreakable nylon	each

FIXTURES

Qty	Description	Unit
16	LED 4" Recessed Can — IC rated, dimmable, 90 CRI, 3000K	each
8	LED Flush Mount Ceiling Fixture — 15" round, 3000K, dimmable	each
6	Combination Smoke / CO Detector — Hardwired with battery backup, interconnect	each
2	LED Wall Pack — Exterior, dusk-to-dawn, 4000K	each

BOXES & ENCLOSURES

Qty	Description	Unit
30	4" Square Box — 2-1/8" deep, 1/2" & 3/4" KO	each
20	Single Gang Old Work Box — 14 cu in, for retrofit locations	each
30	4" Square Mud Ring — Single gang, 5/8" rise	each
10	4" Square Mud Ring — 2-Gang, 5/8" rise	each
6	4-11/16" Square Box — 2-1/8" deep, for junction points	each

CONDUIT — EMT (Chicago Code)

Qty	Description	Unit
-----	-------------	------

40	1/2" EMT Conduit — 10ft sticks	stick
10	3/4" EMT Conduit — 10ft sticks	stick
60	1/2" EMT Set-Screw Connector	each
20	3/4" EMT Set-Screw Connector	each
60	1/2" EMT Set-Screw Coupling	each
15	3/4" EMT Set-Screw Coupling	each
40	1/2" One-Hole EMT Strap	each
15	3/4" One-Hole EMT Strap	each

SUPPLIES & MISC.

Qty	Description	Unit
3	Wire Connectors — Assorted (100pk), winged twist-on	pack
2	Electrical Tape — 3M Super 33+, black (10pk)	pack
1	Grounding Pigtails — 12 AWG green with screw, 50pk	pack
2	Anti-Short Bushings — 1/2" (100pk)	pack
1	Anti-Short Bushings — 3/4" (50pk)	pack
1	Panel Schedule Cards — 40-circuit, pack of 5	pack
1	Circuit Directory Labels — Roll	roll

BLACKTECH SOLUTIONS CORP | 14076 Lincoln Ave, Dolton, IL | (312) 965-2782

Please reply with pricing to: invoices@blacktechsolutionscorp.com

Project: 4823 S Prairie Ave, Chicago, IL 60615 | BSC-E-2026-PR002 & PR003 | Full Project (Phase 1 + Phase 2)