



BLACKTECH SOLUTIONS CORP

Professional Electrical Contractors
10052 S Forest Ave, Chicago, IL 60628
(773) 754-8390 · payroll@blacktechsolutionscorp.com
EIN: 82-3394717

ESTIMATE

Est #: BSC-E-2026-IPA001

Date: June 10, 2026

Valid: 30 Days

Job #: BSC-JOB-IPA001

PREPARED FOR

Richelle Moreno

IPA Express / 8711 LLC
(708) 200-9981

JOB SITE

8711 S 77th Ave

Bridgeview, IL 60455
ComEd Acct: 8350867000

PROJECT

Full Building LED Retrofit

Vendor: Production Distribution Co.
Fixtures: ~275 total
Areas: Office, Warehouses 1–4, Bays

SCOPE OF WORK

- Remove and replace all existing lighting fixtures throughout entire facility
- Install LED Track Fixtures (35W) — Office, Lobby, Storage, 2nd Floor areas
- Install LED Strip Fixtures 4ft (40W) — Warehouses 1, 2, 4, Bays 20–22, 2nd Floor
- Install LED Strip Fixtures 8ft (232W) — Warehouses 1, 2, 4, Bay 21 & 22, Bay 20–14
- Install LED Downlights 8" Round (75W) — Office areas (32 units)
- Install LED High Bay Fixtures (240W) — Warehouse 2 (1 unit)
- All work performed per NEC code · Permits as required
- Materials supplied by Production Distribution Companies (PDC)

271,868

CURRENT KWH/YR

97,687

NEW KWH/YR

\$26,127

ANNUAL SAVINGS

\$2,177

MONTHLY SAVINGS

MATERIALS — PRODUCTION DISTRIBUTION CO. (PDC)

#	PART NUMBER	DESCRIPTION	QTY	UNIT COST	EXTENDED
⚡ LED TRACK FIXTURES					
1	TDRK-24-LS63-G1-FSK	Track 24 LED LS63 G1 FSK 35W	31	\$49.35	\$1,529.85
2	TDRK-24-LS53-G1-FSK	Track 24 LED LS53 G1 FSK 35W	25	\$49.35	\$1,233.75
💡 LED DOWNLIGHTS					

#	PART NUMBER	DESCRIPTION	QTY	UNIT COST	EXTENDED
3	DRS-8R-LS27-G4-9FSK	LED Downlight 8" Round LS27 G4 75W	32	\$64.62	\$2,067.84
 INDUSTRIAL LED STRIP FIXTURES					
4	TSS-4-LS52-SR-G2	LED Strip 4ft LS52 SR G2 40W	120	\$44.65	\$5,358.00
5	TSS-8-LS105-CT-G2-FSK	LED Strip 8ft LS105 CT G2 FSK 232W	66	\$104.58	\$6,902.28
 HIGH BAY FIXTURES					
6	HES-LS240-G1-FSK-HAC-1805	LED High Bay 240W HAC 1805	1	\$217.38	\$217.38
Materials Subtotal (PDC Quote)					\$45,007.14
Materials + 17.5% Markup					\$52,883.39

 LABOR OPTIONS — SELECT ONE

 Option A — Standard (1.15x)	
Estimated Hours	237.2 hrs
Labor Rate	\$113.49/hr
Labor Subtotal	\$26,918.41
Materials Subtotal	\$45,007.14
Combined Subtotal	\$71,925.55
Markup (17.5%)	\$12,586.97
Gross Total	\$84,512.52
 ComEd Rebate Credit	- \$52,000.00
Gross Total	\$84,512.52
CUSTOMER PAYS	\$32,512.52
Customer Initial: _____	
_____ Option A Selected	

 Option B — Full Coverage (1.3x)	
Estimated Hours	268.1 hrs
Labor Rate	\$113.49/hr
Labor Subtotal	\$30,429.51
Materials Subtotal	\$45,007.14
Combined Subtotal	\$75,436.65
Markup (17.5%)	\$13,201.41
Gross Total	\$88,638.06
 ComEd Rebate Credit	- \$52,000.00
Gross Total	\$88,638.06
CUSTOMER PAYS	\$36,638.06
Customer Initial: _____	
_____ Option B Selected	

TERMS & CONDITIONS

- Payment due within 15 days of invoice date · 50% deposit required to begin work
- 1.5% per month late fee on overdue balances · Blacktech Solutions Corp reserves the right to file a mechanics lien
- Estimate valid for 30 days from date of issue · All work performed per NEC and local code requirements
- Permits and inspections included where required · 1-year labor warranty on all installed work
- Materials supplied by PDC — pricing subject to change per PDC quote · ComEd rebate credited directly to customer

Authorized Signature — Blacktech Solutions Corp

Derrell A. Black

Date: _____

Customer Acceptance Signature

Richelle Moreno — IPA Express / 8711 LLC

Date: _____