



BLACKTECH
SOLUTIONS CORP

BLACKTECH SOLUTIONS CORP

Electrical Contractor · Chicago, IL

SHEET #

BSC-MAT-6515-400A

DATE

06/04/2026

VENDOR MATERIAL SHEET — 400A ELECTRICAL SERVICE

JOB ADDRESS

**6515 S Drexel Ave,
Chicago, IL**

CUSTOMER

Rob Moore

SCOPE

400A Service Upgrade

PREPARED BY

Derrell Black

⚡ SERVICE ENTRANCE EQUIPMENT

#	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
1	400A Horizontal Meter Socket / Meter Base — Ring-Type, 4-Gang (CECHA Approved Equipment)	1	Ea	TBD	TBD
2	200A Double-Pole Main Breakers — CECHA Approved (x2, one per meter position)	2	Ea	TBD	TBD
3	200A Distribution Panel (x2 — dual 200A panels)	2	Ea	TBD	TBD
4	Meter Socket Enclosure / Weather Head	1	Ea	TBD	TBD

🔧 CONDUIT & FITTINGS

#	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
5	3½" Rigid Metal Conduit (RMC) — Service Entrance	20	ft	TBD	TBD
6	3½" PVC Conduit (Underground)	10	ft	TBD	TBD
7	3½" Conduit Connectors / Couplings	4	Ea	TBD	TBD
8	3½" Conduit Straps / Clamps	10	Ea	TBD	TBD
9	Conduit Entrance Cap (Weatherproof)	1	Ea	TBD	TBD

🔌 WIRE & CABLE

#	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
10	750 kcmil Aluminum Service Entrance Cable (SER) — Phase A	25	ft	TBD	TBD
11	750 kcmil Aluminum Service Entrance Cable (SER) — Phase B	25	ft	TBD	TBD
12	750 kcmil Aluminum Neutral Cable	25	ft	TBD	TBD

#	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
13	1/0 AWG Copper Ground Wire	100	ft	TBD	TBD
14	750 kcmil Aluminum Compression Lugs / Connectors	6	Ea	TBD	TBD

 GROUNDING SYSTEM

#	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
15	Ground Rod — 5/8" x 8ft Copper-Clad	2	Ea	TBD	TBD
16	Ground Rod Clamps	2	Ea	TBD	TBD
17	Ground Bar / Busbar	1	Ea	TBD	TBD
17a	1" EMT / Rigid Conduit Pipe — Grounding Run	100	ft	TBD	TBD

 BREAKERS & HARDWARE

#	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
18	200A Double-Pole Main Breaker (per panel)	2	Ea	TBD	TBD
19	Branch Circuit Breakers (20A, 30A, 40A — assorted)	1	Lot	TBD	TBD
20	Panel Cover / Dead Front	1	Ea	TBD	TBD
21	Panel Mounting Hardware (screws, anchors, brackets)	1	Lot	TBD	TBD
22	Weatherproof Outdoor Box / Enclosure	1	Ea	TBD	TBD
23	Wire Nuts / Connectors (assorted)	1	Lot	TBD	TBD
24	Electrical Tape, Pulling Lubricant, Misc. Hardware	1	Lot	TBD	TBD

Materials Subtotal	TBD — Pending Vendor Pricing
Electrical Labor (Option 2)	\$18,500.00
Demo Labor	\$1,100.00
ESTIMATED TOTAL\$19,600.00 + Materials	

Note to Vendor: Please provide pricing for all TBD items above. Send quote to invoices@blacktechsolutionscorp.com or call (312) 965-2782.

Note: Quantities are estimates based on field conditions at 6515 S Drexel Ave. Final quantities may be adjusted after on-site assessment.

PREPARED BY

VENDOR / SUPPLIER

Date

Quote Date

Blacktech Solutions Corp | (312) 965-2782 | invoices@blacktechsolutionscorp.com

© 2026 Blacktech Solutions Corp | Licensed & Insured Electrical Contractor | Dolton, IL 60419